SHELBY COUNTY A.D.A. Curb Ramp Installation Program
Spring 2009 - UPDATED

	Intersection	Ramp Configuration	Number of Ramps	Radius Location
1	N. Circle & School Crossing	ST	2	mid-block E, W
2	N. Circle & Breckenwood	SC1*	2	NW
3	Breckenwood & Chesterton	SC1-WT	2	SW, NW
4	Breckenwood & Cedar Town	SC1-WT	2	SE, NE
5	Breckenwood & Chantilly	SC1	2	NE, SE
6	Breckenwood & Carterville	SC1-WT	2	NW, SW
7	Breckenwood & Belfast	SC1	2	NW, SW
8	Breckenwood & Elm River	SC1	2	NW, SW
9	Breckenwood & Englewood	SC1-WT	2	NW, SW
10	Breckenwood & Brandywine	SC1	4	ALL
11	Breckenwood & Pitney	SC1	2	NW, SW
12	Corkwood & Brandywine	SC1	2	SW, SE
13	Corkwood & Cedar Bluff	SC1	2	NE, NW
14	Bitter Creek & Brandywine	SC1	4	ALL
15	Beaverton & Brandywine	SC1	2	NE, NW
16	Broken Oak & Brandywine	SC1	4	ALL
17	Braden & Brandywine	SC1	4	ALL
18	Blacksmith & Braden	SC1	2	NE, SE
19	N. Circle & Braden	SC1	2	N, E
20	Northwood Hills Dr & Egypt Central	SC1	2	NE, NW
21	Northwood Hills Dr & Hunters Glen S	SC1	4	ALL
22	Hunters Glen S & Hunters Glen E	SC1	1	NW
23	Hunters Glen S & Hunt Cliff Trace	SC1	2	NE, NW
24	Hunters Glen S & Hunters Glen W	SC1	1	NE
25	Duncan Rd & Northland Dr	SC1	2	NE, NW
26	Northland Dr & Cedar Bay Dr	SC1	2	NW, SW
27	Cedar Bay Dr & Cedar Bay Cv	SC1	1	NE
28	Northland Dr & North Bay Dr	SC1	2	NE, SE
29	North Bay Dr & Port Haven Dr	SC1	2	NE, NW
30	North Bay Dr & Lake Port Dr	SC1	1	NW
31	Willow Springs Dr & Duncan Rd	SC1	2	NE, NW
32	Willow Springs Dr & Ridge Bay Cv	SC1	2	NW, SW
33	Willow Springs Dr & Hunter Bay Dr	SC1	1	SE
34	Garden Ridge Cv & Hunter Bay Dr	SC1	1	SW
		Ramps this page	72	

* Radius of curb is 40' rad.

WT "Bottom Landing Area" consists of concrete water table. Additional area outside curb ramp is charged as #02950-01-02

SC1 Ramps do not have sidewalk or "Top Landings" behind them

SC2 Ramps have some sidewalk or "Top Landings" behind them which is charged as #02950-02
Note: No SC2 types have been selected in this contract

ST Ramps not within a radius

SHELBY COUNTY A.D.A. Curb Ramp Installation Program
Spring 2009 - UPDATED

	Intersection	Ramp Configuration	Number of Ramps	Radius Location
35	Raible Dr & Bethuel	SC1	2	NW, SW
36	Raible Dr & Martin Rd	SC1-WT	2	NE, SE
37	Martin Rd & Brockman Rd	SC1-WT	2	NE, SE
38	Brockman Dr & Bethuel Rd	SC1	2	NW, SW
39	Martin Rd & Leamont Rd	SC1	2	NE, SE
40	Martin Rd & Woodgreen Dr	SC1	2	NE, SE
41	Martin Rd & Martin West Dr	SC1	2	NE, SE
42	Martin Rd & Martinwood Rd	SC1-WT	2	NE, SE
43	Goodwin Rd & O'Neill Dr	SC1	2	NE,NW
44	O'Neill Dr & O'Neill Cv	SC1	2	NW, SW
45	O'Neill Dr & Betty Lu Dr	SC1	2	SE, SW
46	Betty Lu Dr & Leighton Dr	SC1	2	SE, SW
47	Leighton Dr & Goodwin Rd	SC1	2	NE, NW
48	Godwin Rd & Penny Ln	SC1-WT	2	NE, NW
49	Penny Ln & Betty Lu Dr	SC1	2	SE, SW
50	Godwin Rd & Robena Ln	SC1-WT	2	NE, NW
		Ramps this page	32	
		Total Ramps	104	

* Radius of curb is 40' rad.

WT "Bottom Landing Area" consists of concrete water table. Additional area outside curb ramp is charged as #02950-01-02

SC1 Ramps do not have sidewalk or "Top Landings" behind them

SC2 Ramps have some sidewalk or "Top Landings" behind them which is charged as #02950-02
Note: No SC2 types have been selected in this contract

ST Ramps not within a radius